



US Army Corps  
of Engineers  
Pittsburgh District

# Notice to Navigation Interests

In reply refer to  
Notice No. below

US Army Corps of Engineers, Pittsburgh District  
1000 Liberty Avenue, Pittsburgh, PA 15222-4186  
(412) 395-7650  
[www.lrp.usace.army.mil/or/or-f/navrpt.htm](http://www.lrp.usace.army.mil/or/or-f/navrpt.htm)

---

Notice No. 12-42

Date: September 19, 2012

---

Removal of Flashboards  
Lock & Dam 9, Allegheny River, Mile 62.2

1. **TO ALL WHOM IT MAY CONCERN:** Notice is given that Allegheny Hydro No. 9, L.P. will remove the temporary flashboard system, river conditions permitting, at Lock and Dam No. 9, Allegheny River, Mile 62.2. The work is scheduled to be performed between the hours of 6:00 AM and 6:00 PM daily beginning 3 October 2012 with the anticipated ending date of 17 October 2012.

2. In association with this work, the upper pool will be temporarily drawn down by the hydropower project approximately to elevation 821.7 for the removal of the steel bars and timber boards across the crest of the dam. This elevation equates to an upper pool gage reading of 8.5 or a water level at 0.5 feet below the crest of the dam. This will result in a total change of approximately 1-foot below the normal pool level.

3. Navigators are cautioned to travel within the limits of the navigation channel during this temporary lowering of the upper pool. In addition marina owners and owners of private docking facilities upstream of the dam may be temporarily affected by this work and the associated pool draw down.

FOR THE DISTRICT ENGINEER:

/Signed/  
James R. Fisher  
Chief, Operations Division